



Site Name	Feature Location	6 D's	Reasons	Existing species	Planting notes	Replant species
HUNTER HOUSE ROAD	o/s 188	Damaging	Rooting between kerbs into c/w, f/w mounding rendering f/w effectively unusable	Acer pseudoplatanus	Plant in new pit o/s 188, equidistant between two gateways (same as felled tree)	Acer campestre 'Elegant'
HUNTER HOUSE ROAD	o/s 177	Damaging	Kerbstone missing, f/w damaged, cannot repair without unacceptable root damage	Tilia x europea	Plant in new pit between 175-177, (relocated approx 4m to fall between properties)	Acer campestre 'Elegant'
HUNTER HOUSE ROAD	o/s 238	Damaging	TR: Felling O/S 238 - Kerbs displaced, f/w mounded, stem within c/w at <5.2m	Platanus x hispanica	Plant in new 800mm pit o/s 238 (same as felled tree)	Tilia cordata 'Rancho'
HUNTER HOUSE ROAD	o/s 176	Damaging	Kerbs absent, unable to install without root damage, rooting above tarmac level in f/w also	Tilia x europea	Plant in new 800mm pit o/s 176 (same as felled tree)	Tilia cordata 'Rancho'
HUNTER HOUSE ROAD	o/s hunter court, (opp 149)	Damaging	Kerb line displaced - unable to realign without significant root damage	Acer pseudoplatanus	Plant in new pit opposite 149 (same as felled tree)	Acer campestre 'Elegant'
HUNTER HOUSE ROAD	o/s 145	Damaging	Extensive kerb displacement - unable to realign without significant root damage	Tilia x europea	Plant in new pit o/s 145 (same as felled tree)	Acer campestre 'Elegant'
HUNTER HOUSE ROAD	o/s 155	Damaging	Extensive kerb displacement - unable to realign without significant root damage, lateral rooting through tarmac in f/w also, will be damaged upon planing off	Platanus x hispanica	Plant in new 800mm pit o/s 155 (same as felled tree)	Tilia cordata 'Rancho'
HUNTER HOUSE ROAD	o/s 167	Damaging	Kerbs displaced, no way at all to repair with tree insitu	Tilia x europea	Plant in new 800mm pit o/s 167 (same as felled tree)	Tilia cordata 'Rancho'

HUNTER HOUSE ROAD	o/s 181	Damaging	Kerbstone missing, f/w damaged, cannot repair without unacceptable root damage	Tilia x europea	Plant in new 800mm pit o/s 181 (same as felled tree)	Tilia cordata 'Rancho'
----------------------	---------	----------	--	-----------------	--	------------------------